

SECTION 09 51 00

WHITELINE® Acoustical Ceiling Panels

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Lightweight lay-in-applied acoustical ceiling panels.
- B. Related Sections:

EDIT NOTE: ADD OR DELETE SECTIONS PER PROJECT REQUIREMENTS.

- 1. Section 09 53 00 – Acoustical Ceiling Suspension Systems.
- 2. Section 09 51 00 – Acoustical Ceilings.
- 3. Section 09 21 16 – Gypsum Board Assemblies.
- 4. Division 21 – Fire Suppression.
- 5. Division 23 – Mechanical. Diffusers, vents, and other mechanical items.
- 6. Division 26 – Electrical. Lights and other ceiling mounted electrical items.

1.2 SYSTEM DESCRIPTION

- A. Acoustical Performance Requirements:
 - 1. NRC (Noise Reduction Coefficient): Comply with ASTM C423-90a.

1.3 SUBMITTALS

- A. Comply with Section 01 33 00 – Submittal Procedures.
- B. Product Data: Manufacturer's technical data for each type of panel and baffle including fire-resistive characteristics, finishes, details of installation, and the following:
 - 1. Manufacturer's installation instructions.
 - 2. Certified test reports indicating compliance with Performance Requirements specified herein.
- C. Samples: 2 full size sets of Samples of each specified panel for color selection or verification.
- D. Closeout Submittals: Comply with Section 01 77 00 – Closeout Procedures.
 - 1. Operating and Maintenance Manual, including cleaning and maintenance instructions.
 - 2. Extra Material for Owner's stock.
 - 3. Material Safety Data Sheets (MSDS).

1.4 QUALITY ASSURANCE

- A. Single Source Responsibility: Obtain panel units for entire Project from a single manufacturer.
- B. Manufacturer's Qualifications: Firm with not less than Closeout Submittals: Comply with Section 5 years experience in manufacturing of products similar in complexity to those required for this Project.
- C. Installer's Qualifications: Firm with not less than 5 years experience in installation of products similar in complexity to those required for this Project, including specific requirements indicated.
 - 1. Successfully completed not less than 5 comparable scale projects.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Comply with Section 01 60 00 – Product Requirements.

- B. Deliver and store materials in manufacturer's original unopened containers with brands, names, and production lot numbers clearly marked on these containers.
- C. Storage and Protection: Comply with manufacturer's recommendations.
 - 1. Store products in a cool, dry place out of direct sunlight.
 - 2. Protect from elements and from damage.

1.6 PROJECT CONDITIONS

- A. Environmental Requirements within building:
 - 1. Panels do not require special environmental conditions.
 - 2. Systems may be installed at any stage of construction.

1.7 WARRANTY

- A. Provide manufacturer's written warranty per Section 01 77 00 – Closeout Procedures.

1.8 MAINTENANCE

- A. Extra Materials:
 - 1. Deliver not less than the following quantity of each type, color, and pattern of material, exclusive of material required to properly complete installation.

EDIT NOTE: RETAIN AMOUNT OF EXTRA MATERIALS USED ON PROJECT. DELETE THIS ARTICLE IF NO EXTRA MATERIALS REQUIRED OR ACCEPTABLE.

- a. 3 percent.
 - b. 5 percent.
 - c. 1 carton.
- 2. Furnish Extra Materials from same production run to verify run for color.
- 3. Package replacement materials with protective covering, identified with appropriate labels.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Subject to compliance with requirements, provide products from the following manufacturer:
 - 1. pinta acoustic, inc.
3800 Washington Avenue North
Minneapolis, Minnesota 55412
Telephone: 800-662-0032
612-520-3620
Fax: 612-521-5639
Website: www.pinta-acoustic.com
E-mail: sales@pinta-acoustic.com

- B. Substitutions: Comply with Section 01 60 00 – Product Requirements.

2.2 MANUFACTURED UNITS

- A. Acoustical Ceiling Panels: Sag-resistant foam panel consisting of lightweight, open-cell willtec® foam, laminated on both sides with white fleece.
 - 1. Density: 0.5 to 0.7 pounds per cubic foot (0.23 to 0.32 kg per m³).
 - 2. Tensile Strength: 8 psi (0.06 MPa).
 - 3. Elongation: 8 percent per ASTM D3574-77
 - 4. Fire resistance: Class 1 per ASTM E84.
 - 5. Flame Spread: 0.

6. Smoke Density: 65.

EDIT NOTE: RETAIN PANEL SIZE REQUIRED FOR PROJECT AND DELETE SIZES NOT REQD.

7. Size: Nominal 24 inch by 24 inch (610 mm by 610 mm).
8. Size: Nominal 24 inch by 48 inch (610 mm by 1219 mm).
9. Size: Nominal 48 inch by 48 inch (1219 mm by 1219 mm).
10. Size: Nominal 48 inch by 96 inch (1219 mm by 2438 mm).
11. Size: Custom sizes indicated on Drawings.
12. Panel Thickness: 0.6 inch (15 mm) total thickness.

EDIT NOTE: SELECT ONE OF THE FOLLOWING PATTERNS. DELETE DESIGNS NOT REQUIRED FOR PROJECT.

13. Edge: Square Lay-In.
14. Face Finish: Smooth.
15. Finish: White.

EDIT NOTE: SELECT PANEL COLOR ABOVE OR BELOW. DELETE PANEL COLOR NOT REQUIRED FOR PROJECT.

16. Sound Absorption Coefficients: Type E mountings (16 inch air space), ASTM C423-90a.

<u>Frequencies (Hz)</u>	<u>125</u>	<u>250</u>	<u>500</u>	<u>1,000</u>	<u>2,000</u>	<u>4,000</u>	<u>NRC</u>
0.6 inch:	0.27	0.60	0.64	0.80	0.91	1.02	0.75

17. Acceptable Product: WHITELINE Acoustical Ceiling Panels.

2.3 SUSPENSION SYSTEM

- A. Suspension System: Refer to Section 09 53 00 – Acoustical Ceiling Suspension Assemblies for acoustical panel support system.

EDIT NOTE: RETAIN PARAGRAPH ABOVE OR BELOW. USE ANY 15/16 INCH OR 9/16 INCH GRID. 15/16 INCH GRID IS RECOMMENDED BY PANEL MANUFACTURER.

- B. Suspension System: [Architect to insert acoustical tile ceiling system suspension system specifications here.]

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verification of Conditions: Examine areas and conditions under which work is to be performed and identify conditions detrimental to proper and or timely completion.
 1. Do not proceed until unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with manufacturer's instructions and recommendations for installation of acoustical panels:
 1. Coordinate with mechanical and electrical in locating and spacing fixtures, diffusers, and similar items located in ceiling.
 2. Lay out pattern per reflected ceiling drawings. Where not otherwise indicated, lay out in such manner that margins on opposite sides of rooms are equal or greater than 1/2 tile in width.
 3. Where acoustical ceilings of different heights abut, install acoustical material matching ceiling at vertical surface at ceiling break match ceiling, unless otherwise indicated.
- B. Suspension system: Refer to Section 09 53 00 – Acoustical Ceiling Suspension Assemblies for installation requirements.

RETAIN PARAGRAPH ABOVE OR BELOW PER PROJECT REQUIREMENTS.

- C. Suspension System: [Architect to insert acoustical tile ceiling system suspension system installation requirements here.]
- D. Acoustical Panels:
 - 1. Refer to manufacturer's written installation instructions.
 - 2. Install lay-in acoustical ceiling panels flush and level in suspension system.
 - 3. Install panels with hand protection to avoid soiling.
 - 4. Press panels from above to set into grids. Do not pull from face.

3.3 CLEANING

- A. Clean adjacent surfaces and remove unused product and debris from site.
- B. After installation is completed, clean soiled surfaces of materials.
- C. Remove and reinstall improperly installed material.
- D. Remove damaged or discolored material, or material that cannot be properly cleaned, and install new material.

END OF SECTION

willtec® is a product of pinta acoustic, inc.